

# **MBTA Quarterly Safety Report**

**Ronald Nickle, Chief Safety Officer** 

May 1, 2017



### **Quarterly Safety Report**

- Workplace Safety Improvement Initiative
- Regulatory Updates
  - FTA & DPU regulations
  - FTA General Safety Directive 17-1
  - FRA System Safety Program
- Derailment Prevention Steps Already Taken or Ongoing
  - Risk Mitigation & Corrective Action
  - 20 Year Derailment Data Review
- Safety Certification
  - Infrastructure Projects
  - Vehicle & Systems Procurements



# **Moving from Safe to Safer**

- MBTA is currently in compliance with national transit agency safety standards
- MBTA is taking voluntary steps to enhance safety
- MBTA now has 5 year safety implementation plan which includes increased training and additional infrastructure
- No mainline derailments since November 2016





# **Workplace Safety Improvement Initiative**

- Phase 1: Occupational Health & Safety Plan (Completion: Sept. 30, 2017)
- Phase 2: System-wide Gap Analysis (Sept 1, 2017 March 31, 2018)
- Phase 3: Implementation Plan (March 1, 2017 Onward)







### Regulatory Updates – FTA & DPU Regulatory Changes

- FTA Final Rule State Safety Oversight (49 CFR 674)
  - Increased DPU enforcement and safety standard requirements
  - Revisions to DPU's existing State Safety Program Standard (220 CMR 151)
  - Accelerated DPU implementation
- FTA Final Rule Transit Agency Safety Plan (49 CFR 673)
  - Revise MBTA Safety Plan to adopt Safety Management Systems (SMS)
  - Pending final rule release







## Regulatory Updates – FTA General Safety Directive 17-1

- Proposed FTA General Safety Directive 17-1
  - Issued to all rail transit agencies
  - Conduct a system-wide Safety Risk Evaluation (90 days)
    - Collaborative approach with DPU
    - Utilize tools (SMS) to identify and evaluate risks
    - Develop a corrective action plan (DPU)

#### **FTA Definition**

Stop signal, flag, or other indicator overruns: "When a rail transit vehicle fails to stop as required in advance of a stop signal, flag, or other indicator, as specified in a rail transit agency's operating rules and procedures."







# Regulatory Updates – Federal Railroad Administration (FRA)

- FRA System Safety Program (49 CFR 270)
  - Revise MBTA's existing Commuter Rail System Safety Plan
    - Organizational engagement in safety program
    - Hazard and risk approach to safety
    - Management/labor collaboration
    - Management/labor presentation (completed)
  - Submittal Deadline (February 2018)
  - Implementation Plan (3 years)







### **Derailment Prevention Steps Already Taken or Ongoing**


- Speed Enforcement
  - Speed restrictions
  - Ongoing speed audits
  - GPS monitoring (real time data)
  - Radar monitoring (alerts/video)
- Track Maintenance & Engineering
  - Gauge face grinding
  - Ongoing profile grinding
  - Track geometry
  - Optical inspections
  - Ultrasonic testing
  - Track Safety Standards Training
- Vehicle Maintenance & Engineering
  - Type 8 flange lubricator installation 100% complete
  - Type 8 scissor modification replacement about 50% complete





#### **Derailments - Data Review**

## **Yearly Main Line Derailments 1999-2017**







## Safety Certifications – Infrastructure Projects

- Current Projects (136):
  - 24 Bridge & Tunnel
  - 22 Commuter Rail (both North and South Side)
  - 15 Facility Rehabilitation and/or Improvement Projects
  - 31 Rapid Transit, including 11 elevator projects
  - 19 Operational (i.e. Red/Orange Line Infrastructure Improvements)
  - 22 Transit Oriented Development (TOD)
  - 3 System Extensions (GLX, GLX DB, and Wachusett)
- Final Acceptance Safety & Security Certification:
  - Savin Hill Underpass
  - Hingham Intermodal
  - Boston Landing/Brighton Station
  - Riverside Carhouse Work Platforms





## **Safety Certifications – Vehicle & Systems Procurements**

### **Current Vehicle Projects:**

- Bus Procurements
  - CNG/Hybrid (10 Busses/week)
  - 60' Articulating (2 Busses/week)
- Red Line/Orange Line Vehicle
  - Orange Line Mock-up
  - Final Design milestone
  - DPU participation
- Green Line Type 9 Vehicle Procurement
  - Mock-up at Riverside Carhouse
  - Pilot Car First Article Inspection and Testing







## **Safety Certifications – Vehicle & Systems Procurements**

### **Current Systems Projects:**

- Green Line Train Protection System (GLTPS)
  - Procurement phase
  - Proof of concept approach
- Positive Train Control (PTC) Commuter Rail
  - Safety Certification Committee
  - PTC System Safety and Certification Plan







## **Questions?**



