

# **DGM Remarks**

Fiscal & Management Control Board April 2, 2018





## **Blue Line Signals Operations**

Blue Line vehicles are fully controlled by operators in terms of transit operations and customer interactions (opening/closing doors, announcements, etc.).

The Blue Line Signal System provides traffic and safety information to operators similar to the Green Line or typical automobile signals

- Red The signal system has detected an issue ahead of the operator that requires attention before transit can resume (train can be occupying adjacent 'block')
- Yellow Proceed with caution as traffic may be ahead; Typically seen when a train is at the minimal safe distance away from another train
- Green Proceed as normal

A safety mechanism, called a Mechanical Trip Stop, is installed to assure adherence to **Red** signals. When a train approaches a **Red** signal, the trip stop is activated and in an upright position. Upon receiving a **Green** signal, the trip stop electromechanical system lowers the trip allowing the vehicle to pass.



#### **Blue Line Signals Current State**

Mechanical Trip Stop is a technology invented in the early 1900s and is still used for signal adherence

- Purpose: Serves as an emergency braking mechanism
- Operation: Mechanical pin hangs from the train and a "T" shaped stop is fixated to the ground. When a violation occurs, the pin hits the stop and the trains emergency brake system is applied.
- Requires constant equipment replacement and repairs
  - 150 of mechanical trip stops across entire Blue Line network
  - > 4,680 mechanical actuations a month per trip stop
  - > Averages 3 maintenance calls a week

Due to the age of the equipment maintaining the system is expected to become more difficult.



**Installed Mechanical Trip Stop** 



Top View of "T" Stop



## **Study Goals**

- Assess current signal infrastructure and identify potential areas for short term improvements
- Identify and evaluate new signal technologies such as communication based or digital fixed blocked systems.
- Provide initial cost estimates for system alternatives
- Develop preliminary scope of work for identified signals program





## **Status and Timeline**

Action	Date
Development of RFP	Completed
Advertisement	Early April 2018
Selection	Late Summer 2018
Notice To Proceed	Fall 2018
Completion	Fall 2019



# **DGM Remarks**

Fiscal & Management Control Board April 2, 2018